



Notes:

1. Copper To Be Laid Level With Top Of Main Unless Otherwise Directed By Engineer.
2. Corporation Cock To Be Left Open, Meter Angle Valve Left Closed.
3. Add Detector Tape And Tracer Wire To All Pipe.
4. Backfill And Tamp With Select Material To Pad Pipe. See Detail W-1.00.
5. 10 Gauge Solid Copper Tracer Wire; Blue Jacket.
6. Thoroughly Tape Mechanical Connections With Electrical Tape.

<p>APPROVAL</p> <p><i>Paul Muffet</i> 8/6/19</p> <p>EU MANAGER OF ENGINEERING DATE</p>	<p>REVISED</p> <p>AUG 1, 94</p> <p>MAR 1, 98</p> <p>FEB 1, 02</p> <p>FEB 1, 06</p> <p>SEP 1, 09</p>	<p>TOWN OF EASTON AND EASTON UTILITIES STANDARD DETAILS DOUBLE SERVICE INSTALLATION</p>
<p>ISSUED: MAY 1, 1986</p>	<p>AUG 6, 19</p>	<p>STANDARD NO. W-7.00</p>