

NOTES:

- PIPE AND FITTINGS TO BE SCHEDULE 40 PVC OR SDR 35 PER EASTON UTILITIES STANDARDS.
- 2. PROPOSED SEWER LATERAL OR CLEANOUT CONSTRUCTION TO BE PER EASTON UTILITIES STANDARDS.
- 3. EXISTING SEWER MAIN SIZE, MATERIAL AND DEPTH AS INDICATED IN PLANS. CONTRACTOR TO NOTIFY EASTON UTILITIES ENGINEERING DEPARTMENT.
- 4. ALL LATERALS DISTURBED BY CONSTRUCTION ACTIVITIES SHALL BE REPAIRED BY CONTRACTOR.
- 5. IN CASES OF SEWER MAIN REPLACEMENT, CONTRACTOR TO TIE PROPOSED LATERALS AT MAIN INTO EXISTING LATERALS WITHIN PRIVATE PROPERTY AS SHOWN ABOVE.

	APPROVAL	REVISED	
SON DAY	EU ENGINEERING DEPARTMENT		EASTON UTILITIES STANDARD DETAILS
Life. Made better.	1/31/2024 DATE		SEWER LATERAL RESTORATION
	ISSUED: JANUARY 2024		STANDARD NO.: SS-102.5